

BRUHAT BANGALORE MAHANAGARA PALIKE


BBMP/2013-14/RD/WORK_INDENT9228/CALL-2

APPROVED SCHEDULE - B**Tender Notification No: No.EE/BTP/BBMP/E-PMT/16/2013-14, Date: 06.12.2013****Name of Work: Estimate for the Improvements of Drain and Cement Concrete road in Kodigehalli A.K. Colony in ward No. 08 (Kodigehalli) Kodigehalli sub division.**

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				DANANJAYA B R	
				In Figures	In Words
1	269.98	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 125/ Item No. 19.1/ PWD SR 2013-14	cum	65.22	Rupees Sixty Five and Twenty Two Paise Only
2	8.91	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3/ PWD SR 2013-14	cum	150.22	Rupees One Hundred Fifty and Twenty Two Paise Only
3	179.00	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2013-14	cum	77.46	Rupees Seventy Seven and Forty Six Paise Only

4	153.44	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2013-14	Cum	4247.93	Rupees Four Thousand Two Hundred Forty Seven and Ninety Three Paise Only
5	44.82	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19/ Item Np. 4.46/ PWD SR 2013-14	Cum	5583.36	Rupees Five Thousand Five Hundred Eighty Three and Thirty Six Paise Only
6	29.13	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached lasters,bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 17/ Item No. 4.31/ PWD SR 2013-14	Quin tal	7306.91	Rupees Seven Thousand Three Hundred Six and Ninety One Paise Only
7	410.48	RCC Precast covering slab for drain (10cm thick)	sqm	268.37	Rupees Two Hundred Sixty Eight and Thirty Seven Paise Only
8	105.00	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Page No. 19/ Item No. 4.48/ PWD SR 2013-14	sqm	1232.55	Rupees One Thousand Two Hundred Thirty Two and Fifty Five Paise Only

9	89.50	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Page No. 19/ Item No. 4.48/ PWD SR 2013-14	Cum	6400.23	Rupees Six Thousand Four Hundred and Twenty Three Paise Only
---	-------	--	-----	---------	--


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92